

CORRIGENDUM - 1

Date: 20.03.2023

Tender Ref No: GAD/47/206/2022-23/F – Air Conditioner dated 17.03.2023

Section	Page No	Parameters	Existing Specification	Modification
			Tender for supply &	Tender for supply &
Annexure IV (Financial Bid)	9	Heading	installation of Split Air	installation of Split
			Conditioner and Stabilizer	Air Conditioner
Annexure IV (Financial Bid)	9 Sl No 3	Quantity of 1.00 Ton AC	4	6

Sd/-General Manager UBK Gramin Bank Head Office, Coochbehar



<u>Annexure – IV</u>

Financial Bid

Tender for supply & installation of Split Air Conditioner (To be submitted on the letterhead of the company / firm)

S. No.	Particular	UNIT	Qty. (A)	Quoted Make (B)	Rate (C)	Taxes (D)	Total Amount (E) = (C+D) X (A)
1	Providing and Fixing 2.00 Ton, 5 Star BEE Rating Inverter Air Cooled Split Type Air Conditioners complete with indoor unit (IDU), Outdoor unit (ODU), surface / concealed copper Refrigerant piping with insulation (EP Foam pipe section) up to 3 Mtr. (IDU to ODU) copper power cable up to 4 Mtr. (at least 3CX 2.5 Sqmm, PVC Insulation, FRLS copper wire) (IDU to ODU), R-32 Refrigerant , PVC drain pipe (dia 15mm) Remote, suitable for 400/230V +10% of 50 Hz, 1/3 phase AC supply capable of Performing cooling, dehumidification, air circulation of following capacity with scroll/ reciprocating/ rotary compressor, with ODU Stand		4				
2	Providing and Fixing 1.5 Ton, 5 Star BEE Rating Inverter Air Cooled Split Type Air Conditioners complete with indoor unit (IDU), Outdoor unit (ODU), surface / concealed copper Refrigerant piping with insulation (EP Foam pipe section) up to 3 Mtr. (IDU to ODU) copper power cable up to 4 Mtr. (at least 3CX 2.5 Sqmm, PVC Insulation, FRLS copper wire) (IDU to ODU), R-32 Refrigerant , PVC drain pipe (dia 15mm) Remote, suitable for 400/230V +10% of 50 Hz, 1/3 phase AC supply capable of Performing cooling, dehumidification, air circulation of following capacity with scroll/ reciprocating/ rotary compressor, with ODU Stand		4				
3	Providing and Fixing 1.00 Ton, 5 Star BEE Rating Inverter Air Cooled Split Type Air Conditioners complete with indoor unit (IDU), Outdoor unit (ODU), surface / concealed copper Refrigerant piping with insulation (EP Foam pipe section) up to 3 Mtr. (IDU to ODU) copper power cable up to 4 Mtr. (at least 3CX 2.5 Sqmm, PVC Insulation, FRLS copper	Nos.	6				

		তরবহ বার্বব TARBAN ডি নোড, কোচনির eduled Ba	T ₹ IGA	क्षेत्र KSI	ीय IETR	यार YAG	Road, Coochbehar
	wire) (IDU to ODU), R-32 F drain pipe (dia 15mm) Remote, suitable for 400/230 50 Hz, 1/3 phase AC supply co Performing cooling, dehumid air circulation of following ca scroll/ reciprocating/ rotary co with ODU Stand	IV +10% of apable of ification, pacity with					
	Providing and fixing extra copper piping with insulation after 3Mtr.	(A) 9.53 mm	RMT				
4		(B) 15.88mm	RMT				
5	Providing and fixing wall mounted ODU stand for split air conditioning and all accessories etc.		Nos.	14			
	Grand Total in Fig	gure (Inclusive of a	II)				
	Grand Total in W	ords (Inclusive of a	ll)				

Note:- (Bidder must submit Financial Bid in separate envelope and clearly mention Financial Bid in Bold letters in the top of the envelope and strictly as per the format given above only)

1. L1 will be decided on composite basis.

2. I/We have gone through the terms & conditions as stipulated in the tender enquiry document and confirm to accept and abide the same.

3. No other charges would be payable by the Institute.

Date:	Name	:
Place:	Business Address	:
	Signature of Bidder	:
	Seal of the Bidder	: